# Changes to LEXINGTON® when adding the

# MODULAR CONVERSION OPTION

## **FLOOR**

- Reusable Carrier Replaces Permanent Chassis
- Basement Stairwell
- 2 X 10 Floor Joists 16" on Center (Double 2 X I0 at Perimeter)
- Double 2 X 12M Marriage Line Joists
- 23/32" Tongue and groove Floor Decking
- 2 X 6 Sill Plate

# **MECHANICAL**

- · Furnace and Ductwork by Others
- Return Air Grills

## **PLUMBING**

- Water Heater and Plumbing by Others
- Through-The-Floor Water Lines Stubbed
- Through-The-Floor Drain Lines Stubbed
- Exterior Frost Free Faucet
- Basement Plumbing Vent

# SIDEWALL / SHELL

- 90 Mph Wind Zone
- 2 X 6 Sidewall Construction with Double Top Plate
- 2 X 4 Marriage Wall Construction with Double Top Plate

# **INSULATION**

- No Floor Insulation
- R-40 Ceiling Insulation

#### **ELECTRICAL**

- 200 Amp Service
- Smoke Alarm in Basement Ships Loose
- Field-Connected 3-Way Switch in Stairwell
- Exterior Recept
- Thermostat Wire

#### ROOF

40# Construction Zone – 3/12 Roof is Standard and 5/12 Roof is Optional

#### **EXTERIOR**

- House Wrap
- 7/16" O.S.B. Exterior Sheathing

# TAPE AND TEXTURE APPLICATION AND INTERIOR

- Finished Drywall Throughout
- Upgrade Door Trim, Window, Base and Ceiling Coves

#### **BATH AND KITCHEN**

- Ceramic Backsplash
- Single Lever Faucets